

with Central Network Controller

POWER

NETWORK

STATUS

DEVICE

RAPER®

2. ALL SHOP DRAWINGS, NOTATIONS, AND DIMENSIONS MUST BE APPROVED BY THE PURCHASER IN ORDER FOR DRAPER TO PROCEED FABRICATION.

DRAPER, Inc. 411 S. Pearl Street, Spiceland, Indiana 47385 EMAIL: drapercontract@draperinc.com PH: 765-987-7999

	System Components
1	Intelliflex I/0 Network Device Connecter (NDC3) UL Certified, Plenum Rated Part # C156.311
2	Intelliflex I/0 Network Device Connecter (NDC1) UL Certified, Plenum Rated Part # C156.322
3	Intelliflex I/O Single Zone / Dual Zone Wall Switch Part# C112.161 / C112.162
4	Intelliflex I/O Central Network Controller Part# C156.271
5	Intelliflex I/O Smart Motor Part# C047.300 or C047.303
6	Intelliflex I/O Bus Line - Low Voltage (BY OTHERS) CAT 5E Cable, straight thru connection with RJ45 termination. Overall wire length not to exceed 4000 ft.
7	Intelliflex I/O Motor Data Cable CAT 5E Flat Data Cable, straight thru connection with Low Profile RJ45 termination. 3 ft. Standard Length (see inset for available sizes)
8	Intelliflex I/O Motor Power Cable 120V, 3-Wire Cable (Hot, Neutral, Ground). 1ft. Length Complete with Male M12 Disconnect Plug
9	Extention Cable 120V, 3-Wire Cable (Hot, Neutral, Ground). 5ft. Standard Length (see inset for available sizes) Complete with Female M12 Disconnect Plug
10	Junction Box - by others
11	120V Building Power - by others
12	Roller Shade

		REVISION DESCRIPTION	MM-DD-YY	BY	
	$ \circ $	SUBMITTED FOR REVIEW	04-26-23	BJM	
ENT FROM DRAPER. RAWINGS.	0				
EED WITH MATERIAL	0				
	0				
FAX: 866-637-5611	Ō				